BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

NAME OF THE WORK:-Providing water supply and other works at ward no.07, Byatarayanapura Kodigehalli Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	116.45	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, No. 5 / Item No. 2.1	cum	169.56	Rupees One Hundred Sixty Nine and Fifty Six Paise Only
2	56.01	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. No. 12 / Item No. 4.3 /	cum	5256.36	Rupees Five Thousand Two Hundred Fifty Six and Thirty Six Paise Only
3	6.03	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23 / Item No. 5.6 /	cum	4521.96	Rupees Four Thousand Five Hundred Twenty One and Ninety Six Paise Only
4	2.71	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23 / Item No. 5.9 /	cum	5405.40	Rupees Five Thousand Four Hundred Five and Forty Paise Only
5	116.45	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification No. KBS 2.9 Page No. 6 / Item No. 2.10	sqm	137.16	Rupees One Hundred Thirty Seven and Sixteen Paise Only
6	34.71	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. No. 12/ Item No. 4.6	cum	5876.28	Rupees Five Thousand Eight Hundred Seventy Six and Twenty Eight Paise Only
7	8.32	Providing flooring with 60 cms.x 60 cms. size Vitrified glazed tiles of approved quality & make, fixed on top of existing flooring fixed with suitable adhesive, including cutting the tiles to the required size and fixing etc., complete Page No. 107, Item No. 14.44,	sqm	1154.52	Rupees One Thousand One Hundred Fifty Four and Fifty Two Paise Only

No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	12.00	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS (P.101/I.14.6)	sqm	984.96	Rupees Nine Hundred Eighty Four and Ninety Six Paise Only
9	1.00	Providing revsrse osmosis suystem to cover 2000 Liters of High TDS water per hour **TECHNICAL SPECIFICATIONS** RAW WATER PUMP Purpose:- To feed the Dual Medial filter at pressure more than 2.00 bars which is min operating pressure for filter? **SAND MEDIA FILTER** Purpose:- To remove the total suspendred solids, dirt, iron and reduce silt density index which can foul the members Purpose : To dose anti scaling chemical to protect the scaling formation on RO Membrane MICRON FILTER Purpose : To remove the fine particles ip to 05 microns and reduce silt density levels to acceptable level. HIGH PRESSURE PUMP Purpose : To feed the reverse Osmosis membrane at pressure more than the osmotic pressure taking into consideration flux rate, flow and recovery **RO membrane housing.** Purpose : To remove the major part of TDS into 98% by Reverse Osmosis Membranes arranged and designed to give adequate flow the Recovery. RO CLEANSING SYSTEM ELECTRICAL PANEL Purpose : A control panel is provided as a safety measure for the pumps & other electrical items. Specifications a) Complete starters, overload relays, b) Voltmeter, Ammeter, MCB's indicating lights, c) Rocker switches for Dozers, d) incomers, Auto-Manual switches. INSTRUMENTATION PH DOSING SYSTEM Purpose to dose sodium Bi-carbonate for enhances product water SS till	Nos	946000	Rupees Nine Hundred Forty Six Thousand Only
10	1.00	Providing and Construction of pup panel cabin MS material vetical 50 x 100 mm thick tube, rafter 50 x 100 mm thick rectangle tube 50 x 50 mm thick tuve purlines, roof panel of 30 mm sandwitch puf panel density : 40 kg and wall panel of 30 mm sandwitch puf pannel density : 40 kgs (polyurethane foam) with noth side G I Colour coated sheet ancillaries like C-channels, angles, sealene etc, door of size 1.8 x 2.0 m an alluminium powder coated window of size 1.00 x 2.00 m 1 No of structural glazing (fixed and sliding One side slope as per elclosed drawing cabin of size etc (Approved Quoated Rate) (10 x 8Ft)	Nos	250204.80	Rupees Two Hundred Fifty Thousand Two Hundred Four and Eighty Paise Only
11	99.90	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road. (P-257, It-37.38)	cum	367.20	Rupees Three Hundred Sixty Seven and Twenty Paise Only
12	99.90	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Cement Concrete road. (P-257, It-37.40)	m	655.56	Rupees Six Hundred Fifty Five and Fifty Six Paise Only
13	1110.00	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to depth not less than 15cms with gravel or selected earth available from the excavation etc. complete PRED SR 2012-13 (P-14, It,-3.4.2a) 63mm dia of 6Kg/Cm2	cum	115.36	Rupees One Hundred Fifteen and Thirty Six Paise Only
14	224.74	Refilling the basement and pipeline trenches with selected available earth from trench excavation including watering, Consoldation in layers of 15cm thick including disposing of the surplus earth with a lead of 200 Meters.PRED SR 2012-13 (P-3, It,-1.6)	Nos	115.36	Rupees One Hundred Fifteen and Thirty Six Paise Only

It. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
15	40.00	KSRB 13-6.2-2: Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS . 20mm dia nominal bore.13.2.2/13.3(P-91, It.No.13.27)	Nos	167.48	Rupees One Hundred Sixty Seven and Forty Eight Paise Only
16	40.00	KSRB 13-6.3-7: Providing and fixing in position brass gate valve with C.I.wheel of approved quality (screwed end) 65mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 20mm dia nominal bore.13.37, (P-92, It.No.13.37)	Nos	2175.12	Rupees Two Thousand One Hundred Seventy Five and Twelve Paise Only
17	316.25	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	cum	106.00	Rupees One Hundred Six Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))